

8. Tachometer remains indicating "---r/min".**INSPECTION PROCEDURE**

1	Check of multiplex communications.
----------	---

CHECK:

Are communications normal between combination meter and body ECU.
(Refer to flowchart No.1)

No**Communication failure.
Faulty wiring harness.****Yes****Faulty ECU.
Faulty wiring harness.**